## Source Testing

## How To Plan And Execute A Successful Source Test

#### Michael D. Shroup

Source Evaluation Section Manager
Bureau of Air Quality
South Carolina Department of Health and Environmental Control

Environmental Assistance Conference October 28, 2008

Plan

Plan

Plan

Plan

Decision to Test Hire An Available Test Company
Prepare Test Plan Submit Plan For Approval
The Approval Process Notification

## Test

Compile Data Analyze Audit Samples
Prepare Report Submit Report
Submit Audit Sample Results Report Review/Approval

#### What is the test objective?

Compliance Demonstration?

Emissions Factor Verification or Development?

Establishing Parametric Monitoring Ranges?

**Engineering Study?** 

#### What regulatory time frames must I meet?

Compliance Notifications Test Plan Audit Samples Test Report Other Reports

#### What are other testing considerations?

Access To Sampling Site?
Availability/Installation of Properly Located
Sample Ports?
Appropriate Utilities?
Audit Samples?
Safety Plan?

#### What are other testing considerations?

Do All Appropriate Parties and Persons Know And Understand Their Role And Responsibilities? Production Appropriately Scheduled? Adequate Fuel Supply? Contingency Plan? Special Circumstances?

## Can I get there from here?

#### Site Specific Test Plan Submittal Requirements

**South Carolina** - At least 45 days prior, at least 60 days prior for tests involving Standard 8 pollutants.

NSPS (Part 60) – Silent, Defaults to SC.

NESHAP (Part 61) - Silent, Defaults to SC.

MACT (Part 63) - At least 60 days prior.

#### Site Specific Test Plan Content Expectations

- 1. Facility Information
- 2. Test Objectives
- 3. Process Descriptions
- 4. Safety Considerations

#### Site Specific Test Plan Content Expectations

- 5. Sampling and Analytical Procedures
- 6. Sampling Locations and Documentation
- 7. Internal Quality Assurance/Quality Control (QA/QC) Measures. For each proposed test method when applicable
- 8. Test Report Content

#### Revisions to a Previously Approved Test Plan?

**Any Change** other than the following require the submittal of a revised test plan in accordance with normal regulatory time frames (45-60 days):

- Facility name, address, and telephone number, and name of facility contact.
- Facility permit number and source identification number.

If only the facility information noted above needs to be updated, amendments to the previously approved test plan must be submitted at least 2 weeks prior to the proposed test date.

#### Revisions to a Previously Approved Test Plan!?

Upon notification of the conduct of a source test utilizing a previously approved test plan, the Department may re-review the previously approved test plan. If the plan does not meet our current minimum standards, the plan must be updated and reapproved **PRIOR** to the test being conducted.

Submittal of a test plan or revision

**DOES NOT** 

Constitute notification

#### What Is Proper Notification?

Facility information

Specific approved test plan by date and revision number

Dates of proposed testing

Special information relating to this test

#### **Proper Notification?**

South Carolina - At least two weeks prior NSPS (Part 60) - At least 30 days prior<sup>1</sup> NESHAP (Part 61) - At least 30 days before MACT (Part 63) - At least 60 days before<sup>1,2</sup>

- 1- Except as specified in each subpart
- 2- 30 days for Method 9 not done during other testing

Audit Sample Request?

MACT (Part 63) Sources

At least 30 days before the test you

**MUST REQUEST** 

performance audit samples

What Is Required in A Complete Audit Sample Request?

Test Method(s) For Which Audit Samples Are Requested
Test Date

**Analysis Date** 

**Contact Information** For The Source, Sample Collection Firm, and Sample Analysis Firm Including:

Company Name, Contact Person, Physical (Shipping) Address, Mailing Address, and Phone Number.

What are other testing considerations?

Safety?

Site Preparation?

Clear expectations of all involved parties?

Contingency Plan?

#### **Test Day**

Review With all Present; Site Safety,
Communications, Chain of Command,
Responsibilities and Expectations of All
Involved Parties, Test Plan, Timing, Contingency
Plan, Other Concerns.

#### The Test Report

Test report must be submitted to the Department no later than 30 days after the test is completed unless a different time frame is requested and approved in the test plan.

- a. Summary of the results.
- b. Emission calculations and emission rates in units of the applicable standard, permit limit, etc.
- c. Allowable emission rates in units of the applicable standard, permit limit, etc.
- d. Source compliance status.
- e. Process operating rates.

- f. Methods including actual calculations, equations, and other related information that were used to demonstrate and verify the operating rate during the source test.
- g. Chain of custody records.
- h. Certification of all reference standards used.
- i. Signature of a responsible facility representative who can verify process operating rates and parameters.
- j. Legible copies of all raw laboratory data.

- k. Legible copies of all raw field data.
- 1. Legible copies of applicable stack gas or opacity monitoring system readings.
- m. Legible copies of all applicable process and air pollution control operating parameter readings.
- n. Results of all calibrations and QA/QC measures and checks.
- o. Results of performance audits.

- p. Description of any deviations from the proposed process operations.
- q. Description of any deviations from approved sampling methods/procedures.
- r. Description of any deviations from approved analytical procedures.
- s. Description of any problems encountered during sampling and analysis, and explanation of how each was resolved.

Can I get there from here?



## Questions?

