South Carolina Department of Health and Environmental Control Office of Ocean and Coastal Resource Management 927 Shine Avenue Myrtle Beach, South Carolina 29577

January 15, 2014 Permit Application Public Notice

Henry Garbelman, OCRM-14-018-A

The Department has received an application for a permit for the alteration of a critical area. The application was submitted pursuant to the Coastal Zone Management Act (Act 123) of 1977 South Carolina General Assembly. The application in brief, is described as follows:

LOCATION:

On and adjacent to Canal "Z" at 310 63rd Ave N., North Myrtle Beach, Horry County, South Carolina. TMS: 131-16-05-028.

WORK:


The work as proposed consists of seeking AFTER-THE-FACT authorization to keep an unpermitted floating dock and make maintenance and repair on the structure as needed. Specifically, the applicant seeks to keep the previously installed floating dock and reduce the size to 8' x 8'. The applicant also seeks to adjust the height of the gangway and stairs to avoid being inundated at higher tidal cycles. The work as described is for AFTER-THE-FACT authorization and modifications to a private, recreational use dock.

This public notice is being distributed to all known interested persons and agencies to assist in developing facts on which a decision by the Department can be based. Comments concerning the proposed work must be submitted in writing, setting forth sufficient detail to furnish a clear understanding of the reasons for support or opposition.

Comments regarding this application must be received by the Department on or before <u>January 30, 2014</u>. For more information, please contact: Tanitra Marshall at 843-238-4528 or via email at marshats@dhec.sc.gov.

NOTE:

Plans depicting the proposed work are available and will be provided upon receipt of a written request or may be viewed on the Department website at www.scdhec.gov/environment/ocrm/public notice.htm.



Proposed Work

- 1. Floating dock rebuild reduce to 8' by 8'
- 2. Lower platform raise 17 inches modify stairs
- 3. Piers 6 inch by 6 inch remove both piers

RECEIVED

JAN 1 3 2014


DHEC-OCRM CHARLESTON OFFICE


Henry Janan Openbelman OPM-14-018-A NOTES:

THIS DRAWING IS FOR PERMITTING PURPOSES ONLY AND IS NOT TO BE USED FOR ENGINEERING DESIGN OR DETAIL.

THIS DRAWING IS BASED ON INFORMATION TAKEN FROM AN AS-BUILT SURVEY DONE BY HARRY F. BRUTON & ASSOCIATES.







APPLICANT: MR CHRISTOPHER JERNIGAN & MR HENRY GARBLEMAN
SITE ADDRESS; 310 63RD AVENUE NORTH (UNIT A & B)
SUBDIVISION: N/A

MUNICIPALITY: NORTH MYRTLE BEACH

COUNTY: HORRY

TMS #: 131-16-05-007 / 131-16-05-027

/ 131-16-05-028

VERTICAL DATUM: NGVD 1929

WATERBODY: HOG INLET

DOCK PERMIT

ELEVATION / SECTION A-A'

ORIGINAL DATE: 1/7/2014 REVISED DATE:


SCALE: 1" = 10'

SHEET ___ OF __

DDC PN:



Consulting Engineers, Surveyors, Planners, Landscape Architects & Environmentalists 1298 Professiound Dr., Myrale Beach, SC, 2957



OCRN-14-018-A

Permit Application - Attachment #1

310 63rd Ave N -- Pier Work (Garbelman/Jernigan)

Project Purpose

Project is needed to accomplish critically needed maintenance on the lower deck and floating platform, both of which are in need of repair due to normal wear and tear. The lower platform will be raised to avoid future damage due to rising tides and to replace two damaged piers. Currently, some high tides occur that are above the current lower platform height and have caused water and other damage to the lower platform and structure. The floating platform has exceeded its normal life expectance and cannot be maintained due to damage to its main framing and structure.

Dimensions

Project will <u>retain the existing footprint</u> of the fixed pier, stairs, lower landing and floating platform. It will raise the height of the lower landing by about 17 inches to bring the stairs and landing above high water levels. It will reduce (by 20%) the footprint of the existing floating platform from 8 foot by 10 feet (80 sq ft) to 8 foot by 8 feet (64 sq ft.). Specific project work is indicated on the attached signed and sealed drawings.

General Specification -Scope of Work

Demolition:

- Remove and retain two (2) existing six by six stand alone piling for reuse.
- Remove and dispose of existing 8 by 10 foot floating platform.
- Remove and dispose of existing lower platform and stairs as needed.
- Remove and dispose of two existing damaged pilings on lower platform.

Maintenance:


- Repair by construct of smaller 8 foot by 8 foot floating platform, in current location.
- Remove two damaged pilings and install two reused pilings (pilings noted above).
- Modify new lower pier platform, stairs and railings. Raise platform by two stairs' height (about 17 inches). Rebuild as needed stairs railing, and lower platform.
- Replace ramp from lower platform to floating dock.

RECEIVED

JAN 1 3 2014

DHEC-OCRM
CHARLESTON OFFICE

OCAM-14-018-A



Henry Garbelman OCRM-14-018-A