


CSXT Bramlett Road MGP Site Community Meeting

March 3, 2022





es, U.S. Geological Survey, USDA Farm Service Agency, Map data ©2020 City of500 ft ∟




Agenda

- Remedial Investigation (RI) Addendum
- Neighborhood Sampling
- Best Management Practices (Duke)
- Next Steps

Site History

- Manufactured Gas Plant (MGP)
- Operated 1917 to 1952
- Demolished in 1958
- Migration pathway from MGP toward the south

= Drainage Flow Direction



Pre-Addendum Sampling

LEGEND

SOIL BORING - VISUAL NAPL

VISUAL NAPL

HYDROLOGY


STRUCTURES BUILDING

PARCEL BOUNDARY

SWAMP RABBIT TRAIL

ROAD

FORMER MGP OPERATIONAL




Remedial Investigation Work Plan Addendum


- Assess the Former Stormwater Ditches
- Collect sediment and soil samples along the ditches
- Define the extent of coal tar in ditches

Blue dots are surface


locations



Cross-Section of Ditch-4 from Bramlett Road to Willard Street




Remedial Investigation Report Addendum Results - Sediment



Remedial Investigation Report Addendum Results -Groundwater

Impacted Groundwater is not discharging into the Reedy River


Impacted Groundwater is beneath Parcels 1, 2, and 3





Remedial Investigation Report Addendum Results - Surface Water


Surface Water Quality in the Reedy River is **not** being impacted.






Neighborhood Surface Soil Sampling Phase 2

- 7 Additional Samples Collected at surface and at 2 feet
- Sample results were all within background levels
- Duke Energy installed shallow and deep monitoring wells
- Groundwater sampling results indicated no impacts



Duke installed Best Management Practices as interim measures


- 1. Turbidity Curtain
- 2. Rock Check Dams
- 3. Concrete Cloth used to replace rip rap near discharge to Reedy River





Rock Check Dams

Dams are 167 feet apart within Parcel 5



<u>Upstream rock check dam installation</u> During installation



<u>Upstream rock check dam installation</u> Following heavy rain event



<u>Downstream rock check dam installation</u> Following heavy rain event

Concrete Cloth used to replace rip rap in the ditch south of the Transflo Property

- Removed 257 tons of existing rip rap within the ditch


- Removed 1-foot of sediment from the ditch base



Culvert Ditch Before Work



Concrete cloth installation
Following excavation of rip rap



<u>Concrete cloth installation</u> Installation of culvert extension












Landscaping - Graded and hydroseeded working area near concrete cloth installation

Concrete Cloth used to replace rip rap in the ditch south of the Transflo Property

- Removed 257 tons of existing rip rap and about 1-foot of sediment from the ditch base
- Added an 8-foot culvert extension



Superfund Process





What happens next?

- Remedial Investigation has been completed
- Evaluate remedial alternatives
- Responsible Parties will be engaged to discuss path forward
- Duke Energy will continue to conduct Semi-annual Site-wide groundwater and surface water monitoring and to maintain Interim Measures



CONTACT US

https://scdhec.gov/bramlett

Lucas Berresford, Manager State Voluntary Cleanup Program

Stay Connected









